Statement showing the approximate quantities of work to be done for making good the damages caused to the Lakshmanatirtha Bridge near Hunsur.

Serial No.	Items of work	Quantities
	I. Reconstructing damaged wing for 50′ length.—	
1	Earthwork excavating foundation and removing stuff	393 c. yds.
2	Burnt stone jelley concrete in surki mortar	750 c. ft.
3	Size stone in surki mortar	2,700 „
4	Burnt brick in surki mortar superstructure	7,441 „
5	Rough pointing to stone work and brick work inside with surki mortar	18·4 sqrs.
6	Plastering to brick work, outside with surki mortar	13·52 „
7	Cornice, big	52 ft.
8	Cornice, small	52 ft.
9	Gravelling to conical portion, including watering and consolidation	163 c. yds.
10	Excavating foundation in sandy soil for revetment and removing stuff	16 „
11	New stone revetment, curved portion	80 „
12	Ornamental work for parapet	Lumpsum
13	Sand bag dam during excavation	Do
14	Baling water	Do
15	Removing and uprooting 3 large trees near wing wall	Do
	II. Constructing 3 buttresses to other returns.—	
1	Earthwork excavating foundation for buttresses and removing stuff	226 c. yds.
2	Burnt stone jelley concrete in surki mortar	1,200 c. ft.
3	Size stone in surki mortar foundation	3,240 „
4	Burnt brick in surki mortar superstructure	8 374
5	Rough pointing inside with surki mortar including removing old plaster	1,900 sqr.
6	Plastering in surki mortar	1,560 „
7	Cornice, big	72 ft.
8	Cornice, small	72 ft.
9	Gravelling to conical portions	489 c. yd,
10	New stone revetment	239 „
11	Excavating foundation for revetment in sandy soil and removing stuff	48 „
12	Baling water	Lumpsum
13	Sand bag dam	Do
	III. Gravelling to Bund.—	
1	Excavating top soil and removing the stuff	87 c. yds.
2	Excavating foundation for revetment	123 „
3	Gravelling to bund slopes with watering and consolidation including lead	646 „
4	New stone revetment	405 „
5	Turfing slope	Lumpsum
	IV. Temporary arrangements for accommodating traffic.—	
1	Teakwood posts	31·5
2	Providing iron shoes for same and fixing to post	6
3	Junglewood posts	20 c. ft.
4	Cutting long branches from avenue trees and using as struts, also driving piles, tying arecanut poles, etc.	Lumpsum
5	Gunny bags	226
6	Carthire for bringing two pipes, ropes thick and thin for tying arecanut poles, etc., working charges for preparing iron brackets for truss work, tying ½ round bars, etc., cost of sand, etc.	Lumpsum
7	Arecanut poles	27
8	Laying gunny bags with sand	226
9	Earthwork to bund, with lead, etc.	550 c. yds.
10	Notice boards for giving caution to fast traffic	2
11	Tar	1 tin
12	Bolts	5
13	Iron materials, *e.g.*, flat bars 1″ x ¼″ and round bars ¼″ diameter	Lumpsum
14	Miscellaneous charges including lighting to indicate danger till bridges should be repaired.	Do
	V. Temporary duration of road in river bed during execution of repairs	Do

L. A. H. WINCKLER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE, MYSORE STATE.

Notification No. Roc. 281—*Hc.* 87 *of* 23-24, *dated* 16*th January* 1924.

Sugar-cane setts of different varieties are now available for sale in quantities and at prices noted below on the Experimental Farms at Hebbal and Babbur. Intending purchasers may obtain their supplies direct on application to the respective Farm Managers by the 31st January 1924, on payment of cost which should invariably be made in advance. Delivery of the setts should be taken at the Farm. Arrangements will also be made to consign the

article to destination, if so desired, and work permits, provided, the transport and other incidental charges are borne by the parties concerned and remitted in advance.

HEBBAL FARM.

Variety of cane.	*No. of setts*	*Rate of delivery on the Farm.*
H. M. 544 ...	115,000 single setts	... Rs. 6 per thousand, single setts.
H. M. 312 ...	5,000 do	... do do
H. M. 320 ...	8,000 do	... do do
H. M. 313 ...	5,000 do	... do do
H. M. 553 ...	5,000 do	... do do
H. M. 332 ...	5,000 do	... do do

BABBUR FARM.

H. M. 544 ...	220,000 do	... Rs. 3 per thousand single setts.

LESLIE C. COLEMAN,
Director of Agriculture.

AMRUTMAHAL DEPARTMENT.

Sale Notification dated Mysore 18th January 1924.

A sale of Amrut Mahal cattle will be held at Hunsur, Mysore District, on the 14th and 15th of February 1924. A large number of animals trained both to rope and yoke will be put up for sale. Conditions of sale are notified in the *Mysore Gazette*, page 8 of Part VI, dated 3rd January 1924.

M. ABDULLA SHERIFF,
Offg. Superintendent.

STORES PURCHASE COMMITTEE.

Notice No. 397—S. P. C., dated 21st January 1924.

Sealed tenders will be received in the office of the undersigned for the supply of galvanized iron pipes, etc., noted in the subjoined statement required for the Krishnarajasagara Works. The approximate quantity and description of the articles required are given in the statement and tenders should be sent in the form of that statement duly noting in column left blank, the rate at which the materials will be supplied, which should include also the cost of delivery at Belagola Railway Station, Mysore Railways. *The tenders should reach this office on or before 12 noon on the 7th February 1924,* and be superscribed "Tenders for the supply of galvanized iron pipes for the Krishnarajasagara Works." Earnest money of Rs 100 (which should be only by means of cheques on Imperial or Mysore Banks) as well as samples should accompany the tender, without which the tender will not be considered.

2. The rates given in the tender should hold good for fifteen days from the date fixed for opening the tenders. The whole of the quantity of the material should be supplied within fifteen days from the date the acceptance of the tender is communicated to the tenderer.

3. Final acceptance of the tender will rest with the Stores Purchase Committee who do not bind themselves to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

4. The name of the successful tenderer will be notified in due course and he will be required to deposit as security the amount noted against the article in column 4 and to execute an agreement for the due fulfilment of the contract within eight days of the intimation of acceptance of the tender. The earnest money on rejected tenders will be returned.

5. In case of dispute as to whether the supply of material is similar to that of sample deposited by the firm, the decision of the Stores Purchase Committee shall be final.